

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-00178-00-00
Spot: SESENE Sec/Twnshp/Rge: 13-9S-22W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: BUSS C Well #: 1
County: GRAHAM Total Vertical Depth: 3806 feet

Operator License No.: 31008
Op Name: BOWMAN, PAUL D/B/A PAUL BOWMA
Address: 801 CODELL ROAD
CODELL, KS 67663

PROD Size: 5.5 feet: 3804 125 SX CMT
SURF Size: 8.625 feet: 259 250 SX CMT

\$123⁷⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/04/2004 10:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: LOUIS D BOWMAN Company: PAUL BOWMAN OIL Phone: (785) 434-2286

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Perf at 1850' and 1100'.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/04/2004 2:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

RIH with tubing to 2170' - spotted 100 sxs cement with 400# hulls.
Pulled tubing to 1100' - spotted 80 sxs cement to circulate at surface.
POOH with tubing - squeezed casing with an additional 60 sxs cement.
Max. P.S.I. 300#.
8 5/8" - squeezed 25 sxs cement with 50# hulls.
Max. P.S.I. 300#.

Perfs:

Top	Bot	Thru	Comments
3801	3805		

RECEIVED
OCT 29 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Dennis L. Hamel
(TECHNICIAN)

INVOICED

DATE 10-29-04
SERIAL 2005060723

OCT 07 2004

ANDERSON-PRICHARD OIL CORP #1 BUSS C

13-9-22W 21
SE SE NE

Contr. PEEL-HARDMAN GRAHAM County

E. 2288RB Comm. Comp. 8-17-51 IP 207 BOPD & 22% WTR

Tops	Depth	Datum
ANH	1771	517
HEEB	3453	-1165
LANS	3495	-1207
ARB	3801	-1513
T.D.	3806	-1518

Casing
 8" 259 SWB 15 BOPH/4 HRS
 5" 3804

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

03310 W.M.