

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01155-00-01
Spot: SESENW Sec/Twnshp/Rge: 27-10S-20W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: ROMINE Williams RBMS Well #: 2
County: ROOKS Total Vertical Depth: 3718 feet

KCC
seen
10/29/04
DCC-4

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY
Address: 805 CODELL RD.
CODELL, KS 67663

PROD Size: 5.5 feet: 3712 100 SX CMT
SURF Size: 8.625 feet: 250 150 SX CMT

\$1 120⁸⁴

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/16/2004 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: LOUIS D. BOWMAN &/OR P Company: BOWMAN OIL COMPANY Phone: (785) 434-2286

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Well squeezed at 1170' and 987' w/290 sxs cement and at surface with 30 sxs cement.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/16/2004 12:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Perfs:

RIH with tubing to 1900' - spotted 200 sxs cement with 400# hulls.
Cement circulated at surface.
POOH with tubing and squeezed an additional 25 sxs cement.
Max. P.S.I. 300#.
8 5/8" pressured up to 500#.

Remarks: WELL ALSO KNOWN AS WILLIAMS #2. ALLIED CEMENTING COMPANY.

Plugged through: CSG

RECEIVED
OCT 29 2004
KCC WICHITA

District: 04

Signed Dennis L. Hamel
(TECHNICIAN)

Handwritten initials

INVOICE

Form CP-2/3

DATE 10-29-04
INV. NO. 2005060723

OCT 06 2004

BOWMAN OIL COMPANY
 P.O. BOX 17 #2 ROMINE "OWWO" 27-10-20W
 CODELL, KS. 67630 SE SE NW
 CONTR BILL'S WELL SVC CTY. ROOKS

GEOL _____ FIELD TRIGO
 E 2155 RB CM E 10/1/81 CARD ISSUED 12/31/81 IP P 7 BOPD & WTR
 ARB OH 3709-3718

	+	+
	+	+
	+	+

API NOT ASSIGNED

TOPS	DEPTH	DATUM
HEEB	3382	-1227
LANS	3418	-1263
B/KC	3629	-1474
CONG	3661	-1506
SIMP	3696	-1541
ARB	3707	-1552
TD	3718	-1563

OLD INFO: OPERATOR WAS DERBY OIL CO,
 #2 WILLTAMS, SPD NA, SET 8" 250, 5"
 3709, COMP AS 530 BOPD 8/24/51,
 CONTR: NA
 DST (1) 3496-3505, 1 HR, 150' VHOCM, 15'
 S WTR,
 DP 3714; SWB 1' BOPH; ACID 500; SWB
 5 1/2 BOPH/5 HRS DD 3718; SWB 33 BO/1
 HR, ACID 300 PMP 16 BOPH

NEW INFO: RE-ENTERED EST 10/1/81,
 WSH DWN TO OTD, 5" CSG ALREADY IN
 HOLE, MICT - CO, (ARB OH), AC 250
 G, POP, P 7 BOPD & WTR, 12/28/81

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

IMAGED