

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21149-00-00
Spot: NWSESW Sec/Twnshp/Rge: 8-10S-19W
990 feet from S Section Line, 3630 feet from E Section Line
Lease Name: DICK Well #: 3
County: ROOKS Total Vertical Depth: 3762 feet

Operator License No.: 31008
Op Name: BOWMAN, PAUL D/B/A PAUL BOWMA
Address: 801 CODELL ROAD
CODELL, KS 67663

PROD Size: 5.5 feet: 3755 150 SX CMT
SURF Size: 8.625 feet: 248 190 SX CMT

\$122²⁷

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/21/2004 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: PAUL BOWMAN/DON BOW Company: PAUL BOWMAN OIL Phone: (785) 434-2633

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 10% gel - 500# hulls.
Perf at 1600' and 950'.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/21/2004 1:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Perfs:

RIH with tubing to 2000' - spotted 250 sxs cement with 400# hulls.
Circulated cement to surface.
POOH with tubing and squeezed casing with 40 sxs cement to Max. P.S.I. 400#.
8 5/8" S.P. Squeezed 25 sxs cement with 100# hulls.
Max. P.S.I. 300#. S.I.P. 100#.

RECEIVED
OCT 29 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Dennis L. Hamel
(TECHNICIAN)

HTD.

INVOICED

DATE 10-29-04
INV. NO. 2005060723

Form CP-2/3

OCT 06 2004

RESOURCES INVESTMENT CORP
 3500 ANACONDA TOWER #55
 DENVER, CO 80202 #3 DICK 8-10-19W
 NW SE SW
 CONTR RAINS & WILLIAMSON CTV ROOKS
 GEOL GEORGE OLDS FIELD MARCOTTE

2189 KS 9/14/80 CARD
 2184 GL 1/8/81 ISSUED IP P 12 B0 & 4 BWP
 ARB OH 3755-62

	+	+	+
	-	-	-

API 15-163-21,149

LOG TOPS	DEPTH	DATUM
TOP	3196	-1009
LANS	3444	-1255
ARB	3750	-1567
RTD	3757	-1568
LTD	3759	-1570
DDTD	3762	-1573

B-5/8" 248/190sx, 5 1/2" 3755/150sx
 DST (1) 3583-3635 (LKC)/30-30-30-45
 REC 15' DM W/VSSO, SIP 390-400#
 FP 40-40#, HP 2142-2132#
 MICT - CO, (ARB OH) DD 3762 TB, AC
 500 G (15% HCL) & 250G (28% HCL) W/3 G
 SURFACTANT & 500 G LEASE BRINE W/50#
 HCL SEAL & 750 G (28% HCL) W/1 G
 SURFACTANT PER BBL, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

IMAGED