

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20415-00-01
Spot: NENENE Sec/Twnshp/Rge: 26-12S-21W
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: COTTON Well #: 3
County: TREGO Total Vertical Depth: 3936 feet

Operator License No.: 5453
Op Name: L-K WIRELINE, INC.
Address: PO BOX 1188 E. HIGHWAY 40
HAYS, KS 67601

PROD Size: 4.5 feet: 3932 500 SX CMT
SURF Size: 8.625 feet: 150 500 SX CMT

H 127⁹²

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/20/2004 9:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RANDY K LONGPINE Company: L-K WIRELINE, INC. Phone: (785) 625-6877

Proposed Plugging Method: Ordered 350 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/20/2004 2:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

RIH with tubing to 2350' - spotted 75 sxs cement.
Pulled all tubing - squeezed with 175 sxs cement with 400# hulls.
Max. P.S.I. 500#. S.I.P. 300#.
Tied to 8 5/8" x 4 1/2" annulus - squeezed 50 sxs cement with 100# hulls.
Max. P.S.I. 400#. S.I.P. 200#.
Total of 300 sxs 60/40 pozmix - 10% gel and 500# hulls.
Multiple squeezes from 832' to 2972' with 530 sxs of cement from August 1977 to July 1999.

Perfs:

Top	Bot	Thru	Comments
3932	3936		
3915	3920		
3859	3867		
3704	3708		
3682	3687		
3581	3586		
3545	3550		
3532	3535		
3352	3356		
3310	3317		

Remarks: ALLIED CEMENTING COMPANY. ATS-WATER.

Plugged through: TBG

RECEIVED
OCT 29 2004
KCC WICHITA

District: 04

Signed Roger L. Moses
(TECHNICIAN)

INVOICED
DATE 10.29.04
WF. NO. 2005060727

OCT 26 2004

INDEXED

EDWARD P. LEIKER
 MUNJOR ROUTE
 HAYS, KS.

#3 COTTON

26-12-21W
 NE NE NE

CONTR RED TIGER DRLG. CO.

CTY TREGO

GEOL _____ FIELD ELLIS NW

E 2255 KB CM 8/10/77 CARD ISSUED 10/6/77 IP P 60 BOPD N/W
 LKC 3546-3708

+	+	+
+	+	+
+	+	+

API 15-195-20,415

LOG	TOPS	DEPTH	DATUM
WAB		3310	-1055
HEEB		3510	-1255
LANS		3542	-1287
BKC		3782	-1527
ARB		3906	-1651
RTD		3936*	-1681*

8-5/8" 150/500sx, 4 1/2" 3930/500sx
 MICT - PF 3546-50, 3580-84, SWB 22 BOPH
 N/W, PF 3682-86, SWB 8 BO, AC 1000,
 SWB 16 BOPH, PF 3704-08, PF (ARB)
 3915-19, BP @ 3800, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS