

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20053-00-00  
Spot: NWSESE Sec/Twnshp/Rge: 8-4S-28W  
990 feet from S Section Line, 990 feet from E Section Line  
Lease Name: FRINGER Well #: 2  
County: DECATUR Total Vertical Depth: 4113 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

PROD Size: 5.5 feet: 4098 150 SX CMT  
SURF Size: 8.625 feet: 244 210 SX CMT

#13367

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/09/2004 8:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9169

Proposed  
Plugging  
Method:

Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/09/2004 5:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

RIH with tubing to 3956' - spotted 50 sxs cement with 300# hulls.  
Pulled tubing to 3254' - spotted 17 sxs gel - 72 sxs cement with 200# hulls.  
Pulled tubing to 948' - circulated cement to surface with 83 sxs cement.  
Pumped 25 sxs down backside.  
Max. P.S.I. 500#. S.I.P. 200#.  
Pumped 20 sxs down 5 1/2" casing.  
Max. P.S.I. 800#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3950	3953		

RECEIVED  
OCT 29 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Dennis F. Hamel  
(TECHNICIAN)

INVOICED

DATE 10-29-04  
WV. NO. 2005060720

Form CP-2/3

OCT 06 2004

C-G DRLG COMPANY  
WICHITA, KS  
Contr. CO TOOLS

#2 FRINGER  
Cty. DECATUR

8-4-28W  
NW SE SE

Geol. CHUCK MAYFIELD

Pool FRINGER CONF

E. 2763 KB Cm. 7/15/68 Cp. 8/29/68 IPP 71 BOPD + 17%W

LKC 3950-53, GR36

API 15-039-20,053

LOG Tops	Depth	Datum	Csg. 8" 244/210 sx, 5" 4098/150
HEEB	3842	-1079	DST 3900-16/1', 10' O, 6' HOCM BHP 289-238#, FP 42-68#
TOR	3870	-1107	DST 3939-60/1', 50C' GIP, 910'
LANS	3886	-1123	CL GSY O, 90' OCM, BHP 765- 735#, FP 76-366#
TD	4113	-1350	DST 3963-82/60", 180' OCM, 180' SOCMW, 720' WTR, BHP 1344- 1334#, FP 170-493#
			DST 4029-40/1', 2' MD, BHP 35-35# FP 35-35#
			PF /3950-53, A 200C, SWB 700' OB 6 BOPH 2% WTR, FU 1500'/12 HRS, POP, PMP 71 BOPD + 17% WTR.

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

NO CORES

INDEX