

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03553-00-00
Spot: SENWSW Sec/Twnshp/Rge: 35-10S-16W
1650 feet from S Section Line, 3960 feet from E Section Line
Lease Name: KRUEGER UNIT Well #: 105
County: ROOKS Total Vertical Depth: 3560 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

CIBP Size: feet: 3210
PROD Size: 5.5 feet: 3563 200 SX
SURF Size: 8.625 feet: 318 175 SX
UNK Size: feet: 1265 325 SX

115 70

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/29/2004 9:00 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9169

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 500# hulls - 12 sxs gel.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/29/2004 12:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

RIH with tubing to 2100' - spotted 25 sxs cement with 150# hulls and 12 sxs gel.
Pulled tubing to 1200' - circulated with 85 sxs cement and 150# hulls to surface.
POOH with tubing.
Pumped 5 sxs down 8 5/8". Pressured to 500#.
Pumped 35 sxs down 5 1/2". S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3235	3480		
3180	3184		
3009	3015		

RECEIVED
NOV 03 2004
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS O'LEARY #5. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

INVOICED

DATE

11-3-04

NOV. NO.

2005060751

NOV 01 2004

CITIES SERVICE OIL CO

#5

O'LEARY

35-10-16W

23

SE NW SW

Contr.

ROOKS

County

E 2091

Comm.

Comp.

2-20-53

IP 33 BOPD & 53% WTR

Tops	Depth	Datum
DODGE	3241	-1150
KC	3260	-1169
LANS	3262	-1171
TD	3560	-1469

Casing
5" 3560


PERF 3520-29; 3472-78; 3450-56; 3445-49; 3426-30; 3403-13

ACID 15,000; SQZ; PMP 42 BO & 219 BW/24 HRS; DP 3308

PMP 23 BO, 32 BW/8 HRS

PERF 3235-45; ACID 1000,

KRUEGER POOL 39 BO & 32 BW/12 HRS



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

INDEXED