

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-21764-00-01

LEASE NAME Thornburg F

WELL NUMBER 1

4950 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 4 TWP. 16S RGE. 26 (E) or (W)

COUNTY Ness

Date Well Completed 8-25-00 ¹¹⁻¹⁶⁻²⁰⁰⁴ ^{RCP} ^{OBER} ¹⁰⁻¹³⁻⁰⁴

Plugging Commenced 9-27-04 ²⁸

Plugging Completed 9-28-04

RECEIVED

OCT 13 2004

KCC WICHITA

LEASE OPERATOR Mull Drilling Company, Inc.

ADDRESS P.O. Box 2758, Wichita, KS 67201

PHONE#(316) 264-6366 OPERATORS LICENSE NO. 5144

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-31-04 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? On File If not, is well log attached? On File

Producing Formation Warsaw Depth to Top 4495 Bottom 4575 T.D. 4575

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
4495-4575 (Warsaw)	Oil & Water	0	323	8 5/8"	323	None
		0	4574	4 1/2"	4574	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. RU and circulated 7 sxs sand down tbg to cover perfs @ 4494-4520. Pulled tbg to 1630'.

Loaded csg. Pumped 30 sx common cmt w3% cc. RU and perf'd 1200-1201 w/3 1/8" csg gun (4 SPF). Pumped 150 sxs 60/40 w/6% gel down csg. SI csg w/600# and holding. Pumped 35 sxs 60/40 w/6% gel down surface pipe. Pressured to 400#, held. SI surface pipe, backfilled pit. Plugging witnessed by (If additional description is necessary, use BACK of this form.) Steve Middleton.

Name of Plugging Contractor Mull Drilling Company, Inc. License No. 5144

Address P.O. Box 2758, Wichita, KS 67201


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mull Drilling Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Nancy I. Stiner (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Nancy I Stiner

(Address) P.O. Box 2758 Wichita KS



SUBSCRIBED AND SWORN TO before me this 12th day of October, 2004

Tamara J Kohlman
Notary Public

My Commission Expires: October 16, 2005

MULL DRILLING COMPANY, INC.

RECEIVED P.O. Box 74 (620) 594-2403
Sawyer, KS 67134

No 1839

OCT 13 2004

Code# 634 \$2800.-

KCC WICHITA

631 \$170.-

Company MDC

September 27, 20 04

Lease Thornburg "F"

Well No. #1

September 28, 20 04

JTS.	PULLED FROM WELL	EQUIPMENT	JTS.	RAN IN WELL
		Polished Rod		
		Pony Rods		
		Rods		
		Pump		
		Tubing		
		Tubing Subs		
		Barrel		
		Anchor		

RECORD OF ROD BREAKS			
Size & Type Of Rod	Kind Of Break	No. Of Rods Deep	NEW () USED ()

RECORD OF TUBING FAILURE			
Found Hole ()	Split ()	Collar Leak ()	Jt. # _____ Length _____

Job Description: _____
 Remarks: Abandon #634 Comments: TD 4553' parts 4494'-4520'

Remarks	Rig Hours	Super- vison
<u>9-27 MURU MDC DDPV. RU Habiles backhoe + dug 80 bbl pit, dug out bradwin heads. Tallied + THT w/ 57 jts open ended 2 3/8" fly to 1700' FS. SDON</u>	7	
<u>9-28. Rain sent of fly to 3694'. RU swift, put 7 sks of sand down fly to cover perfor. Pulled fly up to 1630', lowered cng + mixed + pumped 30 sks cement w/ 2% CL. THT w/ fly, RD MDC DDPV. RU Peak latitiline, perforated 1200'-1201' w/ 3/8" std cng gun @ 45RF + mixed + pumped 150 sks 60/40 pay w/ 6% gel down cng, pressured to 600#, SE cng. mixed + pumped 35 sks 60/40 pay w/ 6% gel down annulus, pressured to 400#, SE annulus + returned by Steve millerton of KCC, MDC DDPV</u>	9	2

EQUIPMENT	DESCRIPTION	DAYS	PRICE	QTY.	SIZE	PRICE	TOTAL		PRICE
							Rig		
Sandline Chg.									
Casing Swab							16		\$2480.-
Tubing Swab									
Sand Pump									
5 1/2" Orbit Valve									
Valves								1/2	\$180.-
Fishing Tools									\$140.-
Rod Tongs								2	\$170.-
Tubing Tongs			\$100.-			\$20.-			
Standing Valve									
Tubing Stripper Head									
Bit Sub									
Bits									
Packer				1		\$20.-			
									\$2970.-

SIGNATURE - CUSTOMER REPRESENTATIVE


MULL REPRESENTATIVE