

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD #4  
 K.A.R.-82-3-117

API NUMBER 15-023-20055-00-00

LEASE NAME Walz

WELL NUMBER B-1

1320 Ft. from S Section Line

3960 Ft. from <sup>W</sup> Section Line

SEC. 33 TWP. 4S RGE. 42 (X) or (W)

COUNTY Cheyenne

Date Well Completed Nov. 1977

Plugging Commenced 3/7/88

Plugging Completed 3/7/88

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Barfield Oil Corporation

ADDRESS 1512 Larimer St., Suite 400 Denver, CO 80203

PHONE# (303) 572-3743 OPERATORS LICENSE NO. 04526

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on January 11, 1988 (date)

by Sherry Feist (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Niobrara Depth to Top 1292 Bottom 1318 T.D. 1410

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Ogallala Aquifer	Ground Water	Surface	113	8 5/8"	133	0
Niobrara	Gas	1292	1338	4 1/2"	1410	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.  
No casing pulled. Cemented with 85 sacks 60/40 pos, 4% gel, 200# hulls. Mixed hulls with 20 sacks cement, pumped down at 450 P.S.I. to close perforations. Pumped 65 sacks to fill 4 1/2" casing. Shut in at 400 P.S.I. Cut off 4 1/2" and 8 5/8" 4 ft. below surface. Filled with 6 sacks cement to surface. Welded plate on 4 1/2" and 8 5/8". Reclaimed site. Completed 3/15/88  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B. J. Titan Services (Oakley District) License STAN 6

Address P. O. Box 4442 Houston TX 77210

STATE OF Kansas COUNTY OF \_\_\_\_\_, ss.

Gary D. Andrews (Employee of Operator Barfield Oil Corporation) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as stated that the same are true and correct, so help me God.

(Signature) Gary D. Andrews

(Address) 5744 Corporate Center Dr. PO 735

SUBSCRIBED AND SWORN TO before me this 21<sup>st</sup> day of March, 1988

Dennis L. Gantrel  
 Notary Public

My Commission Expires: 2-8-92