

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

**Well Plugging Record**  
**K.A.R. -82-3-117**

API NUMBER 15-185-23271-0000  
LEASE NAME Leon  
WELL NUMBER #2

TYPE OR PRINT

NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

330 Ft. from North Line of Section  
1800 Ft. from West Line of Section  
3231 <sup>150' East of NW Ne Nw</sup> Township 21s Range 12w  
County Stafford

LEASE OPERATOR L. D Drilling  
ADDRESS 7 SW 26th Avenue  
CITY, STATE, ZIP Great Bend, Kansas 67530  
PHONE # 620-793-3051  
Character of Well Dry and Abandoned

SPOT LOCATION  
Section 3231 Township 21s Range 12w  
County Stafford  
Date Well Completed 11/02/04  
Date Plugging Commenced 11/02/04  
Date Plugging Completed 11/02/04

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 2, 2004 (date)  
by Steve Middleton (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes  
Producing Formation(s) D&A Depth to Top Bottom T.D. 3681

Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	240			
Redbeds	Shale	240	312	8-5/8"	298'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet each set.

Received plugging orders 11/02/04 (Steve Middleton). Plugged with heavy mud in hole and between all plugs using 150 sx 60/40 Poz, 6% Gel. Bottom plug @ 3676'-40sx, 2nd plug @ 800'-50sx, 3rd plug @ 340'-50sx and top plug @ 40'-10sx cemented to surface. Plugged Rathole with 15 sx. Plug down at 6:00 pm 11/02/04 by Acid Services. Ticket #9006. SDC reported plugging to KCC on 11/03/04.

Name of Plugging Contractor Sterling Drilling Company  
Licence No. 5142  
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. D Drilling (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) *Gary M. Talbott*  
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 3rd day of November 2004



*Pamela S. Fields*  
(Notary Public)

My Commission Expires: \_\_\_\_\_

*Bu*

# Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (620) 672-9508, Fax 672-9509

## SAMPLE LOG

*Leon #2*  
*3120 KCC*

**LOCATION:** 150' East of Nw Ne Nw  
**API:** 15-185-23271-0000

Section ~~32~~ T 21s R 12w  
Stafford County, Kansas

**OWNER:** L. D Drilling  
**CONTRACTOR:** Sterling Drilling Company, Rig #1

**COMMENCED:** 27-Oct-04  
**COMPLETED:** 02-Nov-04

**TOTAL DEPTH:** **DRILLER**

3681
------

**FEET**  
**LOGGER**

Did not log
-------------

**FEET**

**Ground Elevation:** 1869  
**KB Elevation:** 1878

### LOG

0 -	8 FEET	Top Sand	
8 -	24 FEET	Clay	Water Well
24 -	36 FEET	Sand and Gravel	
36 -	93 FEET	Sandy Clay	
93 -	112 FEET	Sand and Gravel	
112 -	690 FEET	Shales, Sand and Redbeds	
690 -	713 FEET	Anhydrite (Driller)	
713 -	1580 FEET	Shales and Salt	
1580 -	3676 FEET	Limestone, Shale and Dolomite	
3676 -	3681 FEET	Arbuckle	

### CASING RECORDS

#### Surface Casing-8-5/8"

Drilled 12-1/4" hole to 312'. Ran 8 joints of 8-5/8" surface casing. Tally 297.32', set @ 312' KB. Cemented with 275 sx 60/40 Poz, 3% C.C & 1/4# Cello-Flake. Plug down at 5:20 am 10/28/04. Acid Services ticket #9003. Cement did circulate. Welded straps on bottom 3 joints, tacked collars on top 5 joints.

#### Plugging Data:

Received plugging orders 11/02/04 (Steve Middleton). Plugged with heavy mud in hole and between all plugs using 150 sx 60/40 Poz, 6% Gel. Bottom plug @ 3676'-40sx, 2nd plug @ 800'-50sx, 3rd plug @ 340'-50sx and top plug @ 40'-10sx cemented to surface. Plugged Rathole with 15 sx. Plug down at 6:00 pm 11/02/04 by Acid Services. Ticket #9006. SDC reported plugging to KCC on 11/03/04.

### DEVIATION SURVEYS

1/4	degree(s) at	312	feet
2	degree(s) at	3573	feet

**RECEIVED**  
**NOV 05 2004**  
**KCC WICHITA**