

15.073-19399.00-02

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5697Operator: JACKSON BROS. L.L.C.Name & 116 E. 3RD. ST.Address EUREKA, KS. 67045AB oil well XXXXXXX Gas Well SWD Well/ Input Well Other well as hereinafter indicated: Plugging Contractor: SAGE OIL CO.Address: P.O. BOX 12 VIRGIL, KS. 66870Company to plug at: Hour: Day: 3 Month: 9 2004Plugging proposal received from: Company Name: Phone: Were: 50' CEMENT PLUG @ 2400' 50' CEMENT PLUG @ 1000' 250' CEMENT PLUG TO SURFACE.Plugging Proposal Received by: MIKE HEFFERNPlugging attended by Agent: All XXXXXXX Part TECHNICIAN
None Operations Completed: Hour: Day: 8 Month: 9 2004

Actual Plugging Report: BUILT ROCK BRIDGE @ 2425' MIXED & DUMPED 5 SXS CEMENT, RAN TUBING TO 903' PUMPED 20 SXS CEMENT THRU TUBING, PULLED TUBING TO 280' PUMPED 155 SXS CEMENT LOST CIRC. PULLED TUBING OUT LET CEMENT SET OVER NITE, RAN TUBING BACK IN HIT CEMENT @ 408' PUMPED 24 SXS CEMENT TO SURFACE. PULLED TUBING OUT.

Remarks:

(If additional description is necessary, use BACK of this form.)

I observe this plugging.

API NUMBER

7/9/1957

ne-nw-se-se Sec/Twp/Rge 3-26-8 E1080' feet from south section line720' feet from east section lineLease/Well# BARRIER #15County GREENWOODWell Total Depth 2523' feetProduction Pipe: 4.5" Size Feet 2438'Surface Casing: 8 5/8" Size Feet 100'D & A Lic. # 5687 5684RECEIVED
KANSAS CORPORATION COMMISSION
SEP 22 2004

CONSERVATION DIVISION

Signed: Mike Heffern

TECHNICIAN

INVOICED

DATE 10-29-04
2005060725

Bew