

3-7-88

128

6 031047

023-20,055-0000 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- _____
C SE _____, SEC. 33, T 4 S, R 42 W/E

1320 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 04526
Operator: Barfield Oil Corp
Name & Address: 1512 Larimer St. Suite 400
Denver, Colorado 80202

Lease Name Walz Well # B-1
County Cheyenne
Well Total Depth 1875 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 133

Abandoned Oil Well _____ Gas Well _____ X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B. J. Titan License Number _____

Address Oakley, Kansas

Company to plug at: Hour: AM Day: 7 Month: March Year: 19 88

Plugging proposal received from Gary Andrews

(company name) Barfield (phone) _____

were: 8 5/8" set at 133' w/45 sks cwc. 4 1/2" set at 1349' w/50 sks. PBDT 1310'.

Perfs 1292' - 1318'. Order 85 sks 60/40 Poz 4% Gel 400# Hulls. B. J. Titan Cement Co. Idalia Water Truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:30 AM Day: 7 Month: Mar Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 4 1/2" w/85 sks Cement Blend w/2 sks Hulls mixed into Max Psi 450#. Close in Psi 450#. Plug complete. Backside to be checked when pipe is cut off.

RECEIVED STATE CORPORATION COMMISSION

APR 22 1988 4-22-88

Remarks: _____

INVOICED (If additional description is necessary, use BACK of this report) observe this plugging.

DATE 4-12-88 INV. NO. 20434

Signed Carl Goodrow (TECHNICIAN) Carl Goodrow