

3 022653

15.207-19423.00.00

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20040041
NW,NW,SW 1/4 Sec/Twp/Rge S.34-T.26S.-R.16E.
2386 feet from south section line
4669 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: STATE OF KANSAS Fee Fund
Name & FEE FUND PLUGGING
Address _____
AB oil well X Gas Well _____ SWD Well/ Input Well _____

Lease/Well# APT NO. 10W
County WOODSON
Well Total Depth 1000' feet
Production Pipe: 2" Size Feet 1000'
Surface Casing: 8" Size Feet 20'
D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE Lic. # 6372Address: BOX 386, RR4, CHANUTE, KANSAS 66720Company to plug at: Hour: 9:00A.M. Day: 25 Month: 10 2004Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELT 1000' THAT HAD
BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS
MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: _____

CLAYTON P. TITELPlugging attended by Agent: All _____ Part _____ TECHNICIAN None XOperations Completed: Hour: 1:00P.M. Day: 25 Month: 10 2004Actual Plugging Report: 3/4" PIPE WAS RAN INTO THE 2" CASING TO 925'. CEMENTWAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING ATSURFACE. THE 3/4" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUSTO 600'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATEDFROM THE 8" SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENTWAS FILLED FROM SURFACE. 175 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.Remarks: (GPS SESSION PT. NO. 62) (THIS WAS WELL NO. 10W ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed: _____

Clayton P. Titel
TECHNICIAN

RECEIVED
NOV 04 2004
KCC WICHITA

B