

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21784-00-00
Spot: W2 Sec/Twnshp/Rge: 30-33S-32W
2490 feet from S Section Line, 3960 feet from E Section Line
Lease Name: JACQUART Well #: 1-30
County: SEWARD Total Vertical Depth: 2779 feet

Operator License No.: 7457
Op Name: ELDER & VAUGHN INC
Address: PO BOX 18938
OKLAHOMA CITY, OK 73118

CIBP Size: feet: 2660
PROD Size: 4.5 feet: 2776 WITH 125 SX CMT
SURF Size: 8.625 feet: 598 WITH 850 SX CMT

\$90³²

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/29/2004 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed
Plugging
Method:

PUMP 300# HULLS & 50 SX CMT AT FISH. 50 SX CMT AT 630'. 10 SX CMT AT 40'.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 11/01/2004 12:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

BOTTOM SANDED OFF DUE TO GLORIETTA BREAK-IN. RODS & TUBING STUCK IN HOLE. CUT OFF AT 1000'. 1ST PLUG CIRCULATE HOLE WITH MUD & PUMP 50 SX CMT AT 961'. 2ND PLUG PULL OUT OF HOLE TO 630'. LOAD HOLE & PUMP 50 SX CMT. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
2674	2682		
2635	2643		
2613	2620		

RECEIVED
NOV 08 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 961' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 11-9-04
INV. NO. 2005060767

Form GP-2 *[Signature]*