

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-20858-00-01  
Spot: SWSW Sec/Twnshp/Rge: 10-32S-19W  
660 feet from S Section Line, 660 feet from W Section Line  
Lease Name: BIRD Well #: 2-10  
County: COMANCHE Total Vertical Depth: 6250 feet

Operator License No.: 32384  
Op Name: COMANCHE RESOURCES COMPANY  
Address: 6520 N. WESTERN AVE., SUITE 300  
OKLAHOMA CITY, OK 73116

CIBP Size: feet: 5700  
PROD Size: 5.5 feet: 6249 WITH 290 SX CMT  
RBP Size: feet: 5823  
RBP Size: feet: 6108  
RBP Size: feet: 6148  
SURF Size: 8.625 feet: 649 WITH 200 SX CMT

\$ 203<sup>13</sup>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/03/2004 11:15 AM  
Plug Co. License No.: 33115 Plug Co. Name: NORTH STAR WELL SERVICES, INC.  
Proposal Rcvd. from: DENNIS DYE Company: COMANCHE RESOURCES Phone: (405) 368-5927

Proposed Plugging Method: SET CIBP @ 4500'. PLUG AT 1000' WITH 10 SX GEL & 50 SX CMT. PLUG AT 680' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/03/2004 1:10 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5695'. CIBP @ 4500' WITH 2 SX CMT. 1ST PLUG PULL CASING TO 1058' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 660' & SPOT 50 SX CMT. 3RD PLUG PULL TO 40' & SPOT 15 SX CMT. STAYED FULL THROUGHOUT JOB.

Perfs:


Top	Bot	Thru	Comments
6166	6167		
6133	6134		
6117	6118		
6098	6099		
5778	5780		
5040	5452		
5034	5046		
4674	4680		

RECEIVED  
NOV 08 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 4250' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed: (TECHNICIAN)

INVOICE

DATE 11.9.04  
INV NO 2005060765