

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-21130-00-01  
Spot: NENESW Sec/Twnshp/Rge: 14-23S-22W  
2310 feet from S Section Line, 2790 feet from E Section Line  
Lease Name: OSBORNE Well #: 5  
County: HODGEMAN Total Vertical Depth: 4550 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

PROD Size: 5.5 feet: 4520 WITH 300 SX CMT  
SURF Size: 8.625 feet: 1354 WITH 600 SX CMT

4147<sup>88</sup>

Well Type: SWD UIC Docket No: D23634.0 Date/Time to Plug: 11/02/2004 11:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: KIM HAGEN Company: AMERICAN WARRIOR Phone: (620) 275-7461

Proposed Plugging Method: SAND TO 4475' WITH 5 SX CMT. PLUG AT 1374' WITH 20 SX GEL & 60 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/02/2004 1:25 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

ANHYDRITE @ 1350'. SANDED TO 4475' & 5 SX CMT. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 1380' WITH 20 SX GEL & 60 SX CMT. 2ND PLUG AT 530' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4520	4550	OH	

RECEIVED  
NOV 08 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2014' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE 11.9.04  
NO. 2005060763

Form CP-12