

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23250-00-00
Spot: SENENW Sec/Twnshp/Rge: 10-14S-20W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease Name: GOTTSCHALK Well #: 1
County: ELLIS Total Vertical Depth: 3854 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

PROD Size: 5.5 feet: 3849 w/175 sxs cmt
SURF Size: 8.625 feet: 245 w/185 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/02/2004 8:30 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: DALE POE Company: POE SERVICING INC Phone: (785) 475-8629

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/02/2004 11:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 800' - 1575 - 2150'.
TIH with tubing to 2200' - mixed and circulated cement with 180 sxs cement.
POOH. Tied onto 8 5/8" - pumped 50 sxs cement.
Max. P.S.I. 200#. S.I.P. 100#.
Swaged onto 5 1/2" - topped with 70 sxs cement.
Max. P.S.I. 1400#. S.I.P. 1100#.

Perfs:

RECEIVED
NOV 08 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)

NOV 03 2004

DUNNE-GARDNER PETROLEUM, INC.

200 W. DOUGLAS, #250

#1 GOTTSCHALK

10-14-20W
SE NE NW


WICHITA, KS 67202

CONTR COMPANY TOOLS

CTY ELLIS

GEOL ROBERT ELDER

FIELD PLEASANT



ELV 2237 KB SPD 11/12/82 CARD ISSUED 1/27/83 IP P 25 80 & 30 BWPD

2227 GL

PENN (GOR SD) 3835.5-3839

API 15-051-23,250

LOG	Tops	Depth Datum
TOP		3208-971
HEEB		3469-1232
TOR		3490-1253
LANS		3510-1273
BKC		3760-1523
MARM		3804-1567
GOR SD		3835-1598
RTD		3850-1613
LTD		3854-1617

8 5 8 " 245 185SX. 5 1 2 " 3849 175SX

DST (1) 3671-3710 (LANS) 30-30-30-30. REC 20' M. W. OIL SPOTS. SIP 596-574#. FP 72-52 77-49#. BHT 98'

DST (2) 3813-35 (MARM, GOR SD) 30-45-45-60. 75' GIP, REC 720' GWMO (40% OIL, 29% W, 17% G, 6% M). SIP 1035-1024#. FP 110-143 234-289#. BHT 112'

MICT - CO. PF (GOR) 3835.5-3836.5 & 3838-39. W / 4 SPF. AC 250G. SWB LD. GSO. POP. P 25 80 & 30 BWPD. 1 11 83

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS