

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05437-00-00
Spot: NWNESE Sec/Twnshp/Rge: 27-12S-16W
2310 feet from S Section Line, 990 feet from E Section Line
Lease Name: FROELICH E Well #: 8
County: ELLIS Total Vertical Depth: 3450 feet

Operator License No.: 3833
Op Name: SHAIDA, JOHN H.
Address: 4126 NORTH SWEET BAY CIRCLE
WICHITA, KS 67226

L1 Size: 4.5 feet: 1212 w/300 sxs cmt
PROD Size: 7 feet: 3443 w/100 sxs cmt
SURF Size: 10.75 feet: 243 w/125 sxs cmt

112¹³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/01/2004 3:30 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TOM THOLEN Company: SHAIDA, JOHN H. Phone: (785) 735-2734

Proposed Plugging Method: Ordered 400 sxs Swift Multi-Density cement - 750# hulls.
Fluid level 325'. Log Tech perfed at 1225' and 1725'.
Parted tubing at 2200' - 2 3/8" 1200' of tubing left in hole from 2200' - 3449'.
Dakota 344' - 644'; Anhy 1113' - 1153'; Salt 1481' - 1707'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/01/2004 6:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing to 2100'.
Swift Services rigged on tubing and pumped 200 sxs SMD with 600# hulls mixed in.
No circulation into pit area.
Pulled tubing to 1200' - pumped 107 sxs with 125# hulls mixed in - no circulation.
Pulled tubing to 700' - pumped 25 sxs SMD to circulate cement into pit.
Pulled tubing and tied onto 4 1/2" liner with a swedge - pumped 35 sxs SMD.
Max. P.S.I. 300#. S.I.P. 275#.
Rigged onto backside and pumped 2 sxs.
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3436	3450	OH	
3176	3395		

RECEIVED
NOV 08 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET #7395.

Plugged through: TBG

District: 04

Signed

(TECHNICIAN)

INVOICED

DATE

11-9-04

INV NO

2005060773

NOV 04 2004

RECORDED

KEWANEE OIL

#8

FROELICH

27-12-16W
NW NE SE

Contr. LEWIS DRILLING

ELLIS

County

E 1974 RB Comm.

Comp. 5-21-54

IP 83 BOPD

Tops	Depth	Datum
HEEB	3120	-1146
DODGE	3149	-1175
KC	3176	-1202
ARB	3440	-1466
TD	3450	-1476

Casing

10" 240
5" 3443

CO 3450: 5 BFPH, 20%
WTR:

ERRMERAM NE POOL

+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS