

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05435-00-00
Spot: SWNESE Sec/Twnshp/Rge: 27-12S-16W
1650 feet from S Section Line, 990 feet from E Section Line
Lease Name: FROELICH E Well #: 5
County: ELLIS Total Vertical Depth: 3478 feet

Operator License No.: 3833
Op Name: SHaida, JOHN H.
Address: 4126 NORTH SWEET BAY CIRCLE
WICHITA, KS 67226

L1 Size: 4.5 feet: 1169 w/300 sxs cmt
PROD Size: 7 feet: 3469 w/125 sxs cmt
SURF Size: 10.75 feet: 241 w/125 sxs cmt

113⁰⁴

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/01/2004 12:30 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TOM THOLEN Company: SHaida, JOHN H. Phone: (785) 735-2734

Proposed Plugging Method: Ordered 300 sxs Swift Multi-Density cement - 600# hulls.
Fluid level 239'. Log Tech perfed at 1200' and 1775'.
Dakota 380' - 680'; Anhy 1149' - 1189'; Salt 1517' - 1743'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/01/2004 6:40 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing to 2100'.
Swift Services rigged onto tubing and pumped 154 sxs SMD with 400# hulls - circulated cement to surface.
Pulled tubing and tied onto 4 1/2" liner with a swedge - pumped 67 sxs SMD with 200# hulls mixed in with 200# P.S.I.
Well went on small vacuum.
Left set three hours and topped with 11 sxs to fill casing to surface.
Tied onto backside - pumped 24 sxs SMD.
Max. P.S.I. 200#. S.I.P. 175#.

Perfs:

Top	Bot	Thru	Comments
3473	3475	OH	
3213	3433		

RECEIVED
NOV 08 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET #7394

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

INVOICED

DATE 11.9.04
INV. NO. 2005060773

Form CP-2/3

NOV 04 2004

~~DATE~~
~~NO.~~

IMAGED

KEWANEE OIL COMPANY

#5 FROELICH E


27-12-16W
SW NE SE

Contr. _____ ELLIS _____ County
E. 2010RB Comm. _____ Comp. 12-21-51 IP 240 BOPD

Tops	Depth	Datum
HEEB	3157	-1147
LANS	3209	-1199
ARB	3468	-1458
T.D.	3475	-1465

Casing
8" 240
5" 3469

EMMERAN NORTH POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS