

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
December 2003  
**Type or Print on this Form  
Form must be Signed  
All blanks must be Filled**

Lease Operator: American Warrior, Inc.  
 Address: P.O. Box 399  
 Phone: (785) 398-2270 Operator License #: 4058  
 Type of Well: Oil Docket #: \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: 11/5/04 10/13/04 KCC SEM RBDMs 11/12/04 (Date)  
 by: Steve Middleton (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
Mississippian Depth to Top: 4450' Bottom: 4465' T.D. 4465'  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-083-21042-00-02  
 Lease Name: Osborne OWWO KCC SEM 11/12/04 RBDMs  
 Well Number: 2  
 Spot Location (QQQQ): 50' E - SE - SE - NW  
2310' 2920 Feet from  North /  South Section Line  
1600' 2920 Feet from  East /  West Section Line  
 Sec. 14 Twp. 23 S. R. 22  East  West  
 County: Hodgeman  
 Date Well Completed: 4/11/83 9/15/1989 KCC SEM RBDMs 11/12/04  
 Plugging Commenced: 11/5/04  
 Plugging Completed: 11/5/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippian	oil/water	4450'	4465'	8 5/8"	1322'	None
				5 1/2"	4450'	2014'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Sanded off bottom to 4325' with 5 sacks of cement on top, pulled stretch and shot off casing @ 2014'. Pulled casing up to 1350' and mixed 20 sacks of gel and 60 sacks of cement (60/40 poz, 6% gel) and balance plug. Pulled casing to 550' and mixed 40 sacks of cement and placed plug, pulled casing to 40' and mixed 10 sacks cement and place plug, pulled out and topped of 8 5/8", well plugged.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382  
 Address: N. Highway 283, Ness City, KS 67560

Name of Party Responsible for Plugging Fees: American Warrior, Inc.  
 State of Kansas County, Ness, ss.  
Scott Corsair (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
 (Signature) [Signature]  
 (Address) 210 Avenue A, Bazine, KS 67516

**RECEIVED**  
**NOV 12 2004**  
**KCC WICHITA**

SUBSCRIBED and SWORN TO before me this 9th day of November, 20 04  
Bernice Moore My Commission Expires: 2/7/06  
 Notary Public



*[Handwritten initials]*