

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: American Warrior, Inc.

Address: P.O. Box 399

Phone: (785) 398-2270 Operator License #: 4058

Type of Well: SWD Docket #: D-24,874  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 10/25/04 8/11/04 11/2/04 (Date)

by: Steve Middleton (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-083-20747-00-01

Lease Name: Querbach

Well Number: 3 OWWO

Spot Location (QQQQ): 75' WNWSE - SE  
660 Feet from  North /  South Section Line

735 Feet from  East /  West Section Line

Sec. 4 Twp. 23 S. R. 22  East  West

County: Hodgeman

Date Well Completed: 9/16/86

Plugging Commenced: 10/25/04

Plugging Completed: 10/25/04

*KCC  
213  
11/2/04  
RBDMS*

*KCC  
216  
8/26/04  
RBDMS  
11/2/04*

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records |         | Casing Record (Surface Conductor & Production) |       |        |        |            |
|---------------------------|---------|--|-------|--------|--------|------------|
| Formation                 | Content | From   | To    | Size   | Put In | Pulled Out |
| Arbuckle                  | water   | 4948'  | 5087' | 8 5/8" | 1338'  | None       |
|                           |         |  |       | 5 1/2" | 4948'  | 2000'      |
|                           |         |  |       |        |        |            |
|                           |         |  |       |        |        |            |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 3495' and placed 2 sacks of cement on top of plug. Pulled stretch and shot off 5 1/2" casing @ 2000'. Pulled casing to 1360' and mixed 15 sacks of gel and 50 sacks of cement (60/40 poz, 6% gel) and balance plug. Pulled casing to 550' and mixed 40 sacks of cement and placed plug, pulled casing to 40' and mixed 10 sacks cement and place plug, pulled out and topped of 8 5/8", well plugged.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382

Address: N. Highway 283, Ness City, KS 67560

Name of Party Responsible for Plugging Fees: American Warrior, Inc.

State of Kansas County, Ness, ss.

Scott Corsair (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 210 Avenue A, Bazine, KS 67516

**RECEIVED**


**NOV 12 2004**

**KCC WICHITA**

SUBSCRIBED and SWORN TO before me this 9th day of November, 20 04

Bernice Moore  
Notary Public

My Commission Expires: 2/17/06



*[Handwritten mark]*