

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Messenger Petroleum Inc.  
Address: 525 S. Main, Kingman, KS 67068  
Phone: (620) 532-5400 Operator License #: 4706

Type of Well: Gas Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: \_\_\_\_\_ (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)  
Mississippian Depth to Top: 4110 Bottom: 4116 T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-095-21850-0000

Lease Name: Art Simons

Well Number: 1

Spot Location (QQQQ): C - SE - SE - NE  
2310 Feet from  North /  South Section Line

330 Feet from  East /  West Section Line

Sec. 26 Twp. 28 S. R. 8  East  West

County: Kingman

Date Well Completed: \_\_\_\_\_

Plugging Commenced: 10-27-04 *KCC 3EM 11/12/04 CP 2/3 RDMMS*

Plugging Completed: 10-29-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	232.13	
				4 1/2	4198.63	3420

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 4050', bailed 4 sacks, ripped 3501' and 3420', pulled to 1175', pumped 1 hull and 35 sacks, pulled to 750', pumped 1 hull and 35 sacks, pulled to 285', pumped 98 sacks, circulated to surface.

RECEIVED

NOV 12 2004

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 401 West Main, Lyons, KS 67554

KCC WICHITA

Name of Party Responsible for Plugging Fees: Messenger Petroleum Inc.

State of KANSAS County, Kingman, ss.

Jon F. Messenger (Employee of Operator) or Operator on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Jon F. Messenger

(Address) 525 S. Main, Kingman, KS 67068

SUBSCRIBED and SWORN TO before me this 10<sup>th</sup> day of November 20 04  
John M. Wood Notary Public  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 9/9/2006

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*B...*

# Quality Well Service, Inc.

401 West Main  
Lyons, KS 67554

# Invoice

Date	Invoice #
11/01/2004	606

Bill To
Messenger Petroleum, Inc. 525 South Main Kingman, KS 67068

P.O. No.	Terms	Lease Name
	net	Art Simons #1

Description	Qty	Rate	Amount
Rig Time	26.5	135.00	3,577.50T
Trucking Floor	1	90.00	90.00T
Sand	1	35.00	35.00T
Cement	4	9.00	36.00T
Ripping of Pipe	2	140.00	280.00T
Water Truck	4	60.00	240.00T
Backhoe	2	62.00	124.00T
Phone Calls	1	10.00	10.00T
Clerical	1	10.00	10.00T
Wiping Rubber	1	15.00	15.00T
10-27-04 Called in, rigged up, pulled tubing, sanded bottom, loaded hole, dug cellar, tore head off and casing head down, drove in.			
10-28-04 Checked hole sand at 4050', bailed 4 sacks of Portland, set floor, pulled slips, tore head off, ripped 3501', worked no gain, ripped 3420', worked pipe free, pulled to 1175', went in.			
10-29-04 Pumped 1 hull and 35 sacks, pulled to 750', pumped 1 hull and 35 sacks, pulled to 285', pumped 98 sacks cement, circulated to surface, tore down, loaded out.			
<b>Subtotal</b>			\$4,417.50
<b>Sales Tax (6.8%)</b>			\$300.39
<b>Total</b>			\$4,717.89

RECEIVED  
NOV 12 2004  
KCC WICHITA