


15-147-00156-00-00

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

PHILLIPS County. Sec. 25 Twp. 5 Rge. 18 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SE/4 NE/4 NE/4  
Lease Owner V.E. Shaffer  
Lease Name V.E. Shaffer-Donaldson Well No. 1  
Office Address Russell, Kansas.  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced April 20 19 60  
Plugging completed May 12 19 60  
Reason for abandonment of well or producing formation \_\_\_\_\_  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3164 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3164 feet to surface feet for each plug set. 5 inch liner left in bottom of hole and hole sanded up in 7 in Casing to top of liner at 2990 ft; six sacks of cement dumped in bottom of hole with dump hauler; All pipe then pulled from hole and 1 1/4 inch line pipe run down to 485 feet, and hole circulated with 41 sacks of mud, and 30 sacks of cement; 1 1/4 inch pipe then pulled to 150 feet and 30 sacks of cement pumped down through 1 1/4 inch pipe; small pipe pulled and twenty sacks of cement poured in hole forming cement plug to bottom of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 7 1960  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Barnes and Sons Pipe Pulling Co.,  
Address Russell, Kansas.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
V. E. Sheffer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Box 563, Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of July, 19 60

My commission expires July 15, 1960  
Georgiana W Bell Notary Public.

