


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-147-00814-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Phillips County. Sec. 24 Twp. 5 Rge. 18 (E) (W) X

Location as "NE/CNW/SE" or footage from lines SW SE SE

Lease Owner Shawver-Armour, Inc.

Lease Name Grace Jones Well No. 212

Office Address 817 Central Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed _____ 19____

Application for plugging filed December 18, 1957

Application for plugging approved December 20, 1957

Plugging commenced January 6 1958

Plugging completed January 6, 1958

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production December 28 1957

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Lansing Kansas City Depth to top 3115 Bottom 3270 Total Depth of Well 3270 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	water	0	136	8 5/8	136	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it to the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back w/crushed rock to 3110', dumped
3 sax cement @ 3110' w/dump bailer. Top of
cement, 3080'. Pumped in 15 sax Gel-Mud &
20 sax cement @ 575', filled hole w/mud to
135', pumped in 15 sax cement by Sun Cem. Co.
Filled hole w/mud to 35', set rock bridge, dumped
10 sax cement for cap.

RECEIVED
STATE CORPORATION COMMISSION

JAN 28 1958

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shawver-Armour, Inc.
Address 817 Central Building, Wichita, Kansas

128-58

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
JAMES ARMOUR

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Armour
JAMES ARMOUR

817 Central Building, Wichita,
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of January, 1958

My commission expires December 29, 1959

MARJORIE HALL
MARJORIE HALL

Notary Public.

PLUGGING
FILE SEC 24 T 5 R 18 W
BOOK PAGE 71 LINE 7

DRILLING LOG

WELL NAME: Grace Jones # 2
OWNERS: Laura Jane Oil Co.
CONTRACTORS: Laura Jane Oil Co.
COMM: 6-22-51
COMP: 7-2-51

LOCATION: SW SE SE, 24-5-18
Phillips County, Kansas
ELEVATION: 1926 DF
1926 BS
CASING RECORD: 8 5/8" - 136'
3270' 43"
PRODUCTION:

<u>FORMATION</u>	<u>TO</u>			
Soil	25			
Sand	45			
Shale	110			
Lime-Shale	136			
Shale-Shells	665			
Dakota Sand	755			
Red Rock - Shale	1040	Heebner	3040	-1118
Shale-Lime	1130	Toronto	3065	-1127
Shale-Red Rock	1355	Lansing	3080	-1152
Anhydrite	1445			
Shale-Lime	3040			
Heebner Shale	3042			
Shale-Lime	3130			
K. C. Lime	3140			
Lime	3270 TD Rotary (Casing on Bottom)			

I certify that the above is a true and correct copy of the log of the Grace Jones # 2, SW SE SE, 24-5-18, Phillips County, Kansas, to the best of my knowledge.

LAURA JANE OIL COMPANY, INC.

BY: James Armour
JAMES ARMOUR

Sworn and subscribed to before me this 23 day of June, 1957

Wesley Hall
NOTARY PUBLIC

My Comm. expires Dec 29, 1957

PLUGGING
FILE - SEC. 24 T. 5 R. 18W
BOOK PAGE 27 LINE 4

RECEIVED
STATE CORPORATION COMMISSION
JUN 24 1957
CONSERVATION
6-24-58