


15-147-00690-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Phillips County. Sec 24 Twp 25 Rge. 18W (E) (W)  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines SE NW SE  
Lease Owner Laura Jane Oil Co., Inc.  
Lease Name Grace Jones Well No. 3  
Office Address 817 Central Building, Wichita, Kans  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 7-30-51 19 51  
Application for plugging filed 7-30-51 19  
Application for plugging approved 7-30-51 19  
Plugging commenced 12:00 noon 7-30 19  
Plugging completed 2:00 PM 7-30 19  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production none 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. W. Peddy, Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 3500 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface soil			50			
Shale	water	40	60			
Yellow clay & shale		60	125			
Shale		125	145	8 5/8	145	cemented in

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped heavy mud in hole to within 140' of top. Hole set wooden plug @ 140'.  
One sack of cottonseed hulls mixed 15 sacks cement put some on top of plug, filled hole to within 20' of top with heavy mud. Set wool plug. Filled to bottom of cellar with 10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION

AUG 10 1951

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Laura Jane Oil Company, Inc. 8-10-51  
Address 817 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Joe Jacobs (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe Jacobs  
Great Bend Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of August, 19 51

Carol T. Fair  
Notary Public.

My commission expires 6-28-52

PLUGGING  
FILE SEC 24 T 5 R 18W  
BOOK PAGE 99 LINE 41

15-147-00690-00-00

DRILLING LOG

WELL NAME: Grace Jones # 3  
OWNERS: Laura Jane Oil Co.  
CONTRACTORS: Laura Jane Oil Co.  
COMM: 7-20-51  
COMP: 7-30-51

LOCATION: SE NW SE, 24-5-18W  
Phillips County, Kansas  
ELEVATION: 1968 DF  
1970 RB  
CASING RECORD: 8 5/8" @ 144'  
PRODUCTION: Dry

<u>FORMATION</u>	<u>TO</u>
Soil	40
Shale	60
Clay - Shale	125
Shale	740
Dakota Sand	800
Red Rock - Shale	1035
Shale - Lime	1320
Anhydrite	1395
Shale - Lime	2944
Lime	3069
Shale	3072
Lime - Shale	3111
Lime	3452
Arbuckle Lime	3500

<u>TOPS</u>	
Topeka Lime	2867 -897
Heebner Shale	3069 -1099
Toronto Lime	3095 -1125
K C Lime	3111 -1141
Arbuckle Dolomite	3480 -1510

I certify that the above is a true and correct copy of the log of the Grace Jones # 3, SE NW SE, 24-5-18W, Phillips County, Kansas, to the best of my knowledge.

LAURA JANE OIL COMPANY, INC.

BY: James Armour  
JAMES ARMOUR

Sworn and subscribed to before me this 7<sup>th</sup> day of August, 1951.

Coral F. Jant  
NOTARY PUBLIC

MY Comm. expires 6-28-52

**PLUGGING**  
FILE SEC 24-5-18W  
BOOK PAGE 99 LINE 41

**RECEIVED**  
STATE CORPORATION COMMISSION  
AUG 10 1951

8-10-51