

State of Kansas



15-147-20001-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
CONSERVATION COMMISSION  
MAR 7 1967  
3-7-67  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Harre of Thoroughbred Drlg. has this date requested permission to plug the following described well:

Mr. Harre guarantees payment of the plugging fee.

Operator's full Name: National Associated Petroleum Co.,

Complete Address: Fifth Floor, Ritz Bldg., Tulsa, Oklahoma

Lease Name: Ernest Fulghum "A" Well No. 1

Location: SE SE NE Sec. 19 Twp. 5 Rge. 17 (E)(W) X

County Phillips Total Depth 3490' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Harre was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace  
25 sc cement thru drill pipe. Heavy mud to 220' set cementing plug and  
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole with  
2 sc cement.

Very truly yours,

Ray Massey  
Conservation Division Agent