



15-147-20020-00-00

ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 13 1967

11-13-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ogle of Red Tiger Drlg. has this

date requested permission to plug the following described well:

Mr. Ogle guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Inc.

Complete Address: 1515 Wichita Plaza Wichita, Kansas

Lease Name: Keeten Well No. 1

Location: 2200' FNL & 1980' FEL Sec. 17 Twp. 5 Rge. 17 (E)(W) X

County: Phillips Total Depth 3415 Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Ogle was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace  
100 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and  
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing plug  
1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with 2 sc  
cement.

Very truly yours,

Leo F. Massey  
Conservation Division Agent