



15-147-20220-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1976

9-13-76
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Christopher of R & W Drlg. has this

date requested permission to plug the following described well:

Mr. Christopher guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Co.

Complete Address: 435 Page Court, 220 W. Douglas, Wichita, Ks.

Lease Name: Shaw "A" Well No. 1

Location: SW NW NE Sec. 10 Twp. 5 Rge. (E)(W) 18

County: Phillips Total Depth 3375' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Christopher was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 800' thru drill
pipe. Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy
mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Geo Messing
Conservation Division Agent