

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 DERBY BLDG,
WICHITA, KANSAS 67202

Rev. 12-11-80
FORM CP-1

WELL PLUGGING APPLICATION FORM
FILE ONE COPY

API NUMBER 15-147-20,327-0000 (OF THIS WELL)
(THIS MUST BE LISTED, IF NO API# AVAILABLE PLEASE NOTE DRILLING COMPLETION DATE.)

LEASE OWNER Baird Oil Company

ADDRESS Box 7, Logan, Kansas 67646

LEASE (FARM NAME) ELLIOT WELL NO. 1

WELL LOCATION C NW NW SEC. 24 TWP. 5S RGE. 18W (EAST) (WEST)

COUNTY Phillips TOTAL DEPTH 3516' FIELD NAME _____

OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A X

WELL LOG ATTACHED WITH THIS APPLICATION AS REQUIRED? YES
(IF NOT STATE REASON WHY)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 3:30 p.m., 6/06/81

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1981
0-26-81
CONSERVATION DIVISION
Wichita, Kansas

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bill Craig (Toolpusher) ADDRESS 702 S. 2nd St., Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. _____

ADDRESS 801 Union Center, Wichita, KS 67202

INVOICE COVERING ASSESSMENT FOR PLUGGING THIS WELL SHOULD BE SENT TO:

NAME Baird Oil Company


ADDRESS Box 7, Logan, Kansas 67646

AND PAYMENT WILL BE GUARANTEED BY APPLICANT OF ACTING AGENT.

SIGNED: _____

Jack L. Partridge
APPLICANT OR ACTING AGENT
Jack L. Partridge, Vice Pres.

DATE: June 23, 1981



15-147-20237-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	Baird Oil Company
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME: "	ELLIOT #1
LOCATION:	C NW NW, Section 24-5S-18W Phillips County, Kansas
SPUD DATE:	5/22/81
COMPLETION DATE:	6/06/81

0	218	Shale & Sand
218	1378	Shale
1378	1405	Anhydrite
1405	2235	Shale
2235	2759	Lime & Shale
2759	2833	Shale
2833	2930	Lime & Shale
2930	2980	Shale & Lime
2980	3368	Lime
3368	3516	Lime & Sand
	3516	Rotary Total Depth

Spud @ 8:00 p.m., 5/22/81. Drilled 218' of a 12 1/4" hole. Ran 5 joints of 8 5/8" 24# casing set @ 217'. Cemented with 160 sacks of Class A Cement, 2% Gel, 3% Ca. Cl. Plug down @ 2:00 a.m., 5/23/81. Cement did circulate.

3516' RTD. Set 1st plug @ 900' with 65 sacks. Set 2nd plug @ 270' with 30 sacks. Set 3rd plug @ 40' with 10 sacks. Plug was down @ 3:30 p.m., 6/06/81.

SAMPLE TOPS:

Anhydrite
B/Anhydrite

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS
COUNTY OF SEDGWICK


JUN 26 1981
CONSERVATION DIVISION
Wichita, Kansas

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the ELLIOT #1, C NW NW, Section 24-5S-18W, Phillips County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
Jack L. Partridge, Vice Pres.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 23rd day of June, 1981.



Suzanne M. Hofer
Suzanne M. Hofer, Notary Public

STATE OF KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado, Derby Bldg.
Wichita, Kansas 67202

INVOICE and WELL PLUGGING AUTHORITY

July 27, 1981

INVOICE NUMBER: 6077-W

TO: Baird Oil Company, Inc.
Box 7,
Logan, KS., 67646

15-147-20327-00-00

PLUGGING ASSESSMENT AS FOLLOWS:

Elliott #1
C NW NW, Sec.24-5S-18W
Phillips
Abercrombie Drilling, Inc.

\$114.27

NOTE: We also need the following before our file is completed:

- _____ Well Plugging Record (CP-4)
- _____ Well Log
- _____ Well Plugging Application (CP-1)

WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.

PAYABLE UPON RECEIPT

For Administrator



Mr. Marion Schmidt, 2104 Canterbury Rd., Hays, KS., 67601

is hereby assigned to supervise the plugging of the above mentioned well.

RETURN PINK COPY WITH REMITTANCE