

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15 - 147 - 20258 - 00 - 00 (of this well)
Lease Owner Baird Oil Company
Address P. O. Box 7, Logan, Kansas 67646
Lease (Farm Name) HAMMOND Well No. 1 (Twin)
Well Location 20' E C S/2 S/2 SW/4 Sec. 24 Twp. 5 Rge. 18W (E) (W) X
County Phillips Total Depth 3285' Field Name _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 6:00 a.m., May 25, 1979

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:
Harold Maley Address 216 E. McFarland, Hill City, Ks
Plugging Contractor Abercrombie Drilling, Inc. License No. _____
Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to RECEIVED
Baird Oil Company STATE CORPORATION COMMISSION
Address P. O. Box 7, Logan, Kansas 67646 MAY 31 1979

and payment will be guaranteed by applicant or acting agent. CONSERVATION DIVISION
Wichita, Kansas 5-31-79
Signed: Jack L. Partridge
Applicant or Acting Agent
Jack L. Partridge
Date: May 30, 1979

CONTRACTOR'S WELL LOG

OPERATOR: Baird Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Hammond #1 (Twin)
 LOCATION: 20' E C S/2 S/2 SW/4, Section
 24-5-18W, Phillips County, Kansas
 SPUD DATE: May 21, 1979
 COMPLETION DATE: May 25, 1979

0	153	Clay and shale
153	270	Sand and shale
270	520	Shale
520	1385	Shale and sand
1385	1442	Sand and shale
1442	1472	Anhydrite
1472	1820	Sand and shale
1820	2473	Shale
2473	3102	Shale and lime
3102	3285	Lime and shale
	3285	Rotary Total Depth

Spud hole at 1:00 p.m., May 21, 1979. Drilled 270' of 12 1/4" hole. Ran 7 joints of 8-5/8" - 20# casing. Set at 268' RTD. Cemented with 220 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 6:45 p.m., May 21, 1979.

T.D. 3285'. Set 1st plug at 650' with 60 sacks, 2nd plug at 260' with 25 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 6:00 a.m., May 25, 1979.

SAMPLE TOPS:

Anhydrite 1442'
 B/Anhydrite 1472'

RECEIVED
 STATE CORPORATION COMMISSION

MAY 31 1979

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)


CONSERVATION DIVISION
 Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Hammond #1 (Twin) 20' E C S/2 S/2 SW/4, Section 24-5S-18W, Phillips County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 30th day of May, 1979.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.

State of Kansas



15-147-20258-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

May 29, 1979

WELL PLUGGING AUTHORITY

Well No.	1 Twin
Lease	Hammond
Description	20'E C S/2 S/2 SW Sec. 24-5-18
County	Phillips
Total Depth	3285'
Plugging Contractor	Abercrombie Drilling, Inc.


Baird Oil Co., Inc.
Logan, Kansas 67646

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Marion Schmidt, 2104 Canterbury Road, Hays, Kansas 67601
is hereby assigned to supervise the plugging of the above
named well.