

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15 - 147 - 20254-00-00 (of this well)
Lease Owner Baird Oil Company
Address P. O. Box 7, Logan, Kansas 67646
Lease (Farm Name) HAMMOND Well No. 1
Well Location C S/2 S/2 SW/4 Sec. 24 Twp. 5 Rge. 18W (E) (W) X
County Phillips Total Depth 2485' Field Name
Oil Well Gas Well Input Well SWD Well Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 5:30 p.m., May 20, 1979

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Harold Maley Address 216 E. McFarland, Hill City, KS

Plugging Contractor Abercrombie Drilling, Inc. License No.

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent **RECEIVED**
STATE CORPORATION COMMISSION

Name Baird Oil Company **MAY 31 1979**

Address P. O. Box 7, Logan, Kansas 67646

and payment will be guaranteed by applicant or acting agent.

CONSERVATION DIVISION
Wichita, Kansas

5-31-79

Signed: Jack L. Partridge
Applicant or Acting Agent

Jack L. Partridge
Date: May 30, 1979

15-147-20254-0000

CONTRACTOR'S WELL LOG

OPERATOR: Baird Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Hammond #1
 LOCATION: C S/2 S/2 SW/4, Section 24-5-18W
 Phillips County, Kansas
 SPUD DATE: May 17, 1979
 COMPLETION DATE: May 20, 1979

0	274	Sand and shale
274	680	Shale
680	1445	Sand and shale
1445	1475	Anhydrite
1475	1963	Sand and shale
1963	2337	Shale and lime
2337	2485	Shale
	2485	Rotary Total Depth

Spud hole at 2:30 p.m., May 17, 1979. Drilled 274' of 12 1/4" hole. Ran 7 joints of 8-5/8" casing. Set at 272' K.B. with 220 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 8:00 p.m., May 17, 1979.

T.D. 2485'. Plugged with 65 sacks of 50/50 posmix, 6% gel. Plug was down at 5:30 p.m., May 20, 1979.

SAMPLE TOPS:

Anhydrite 1445'
 B/Anhydrite 1475'

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

RECEIVED
 STATE CORPORATION COMMISSION

MAY 31 1979

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is true and correct copy of the log of the Hammond #1, C S/2 S/2 SW/4, Section 24-5-18W, Phillips County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 30th day of May, 1979.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.

State of Kansas



15-147-20254-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

May 29, 1979

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Hammond
Description	C S/2 S/2 SW Sec. 24-5-18W
County	Phillips
Total Depth	2485'
Plugging Contractor	Abercrombie Drig.


Baird Oil Co., Inc.
Logan, Ks. 67646

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Marion Schmidt 2104 Canterbury Rd. Hays, Ks. 67601
is hereby assigned to supervise the plugging of the above
named well.