

KANSAS

FORM CP-3  
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-149-20,355-08-00

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name H. R. M. PETROLEUM CORPORATION

Complete Address 817-17th St. # 820 DENVER COLORADO. 80202

Lease Name BENDER Well-No. #1-35

Location NE-NW. Sec 35 Twp. 5 Rge. 19 (East)(West)

County PHILLIPS Total Depth 2600 <sup>FK</sup>

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor HAN-DRILCO (LARRY HICKS)

Address \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour: 12:00 <sup>PM</sup> Day: 19 <sup>th</sup> Month: NOV. Year: 19 81

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

8 5/8" - 202 FK SB. CMC w/ 155<sup>st</sup> QUICK SET - 2% GEL - 3% CA-CL.

ORDERED 140<sup>st</sup> 50% Formix 4% GEL - 3% CA-CL. + 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1<sup>st</sup> Plug. @ 900 FK w/ 40<sup>st</sup> CNT.

2<sup>nd</sup> Plug. @ 210 FK w/ 40<sup>st</sup> CNT.

3<sup>rd</sup> Plug. = SOLID BRIDGE HULLS - PLUG. @ 40 FK w/ 10<sup>st</sup> CNT.

10<sup>st</sup> IN RAT HOLE.

10<sup>st</sup> IN MOUSE HOLE.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 23 1981  
CONSERVATION DIVISION  
WICHITA, KANSAS

CEMENTED BY HALLIBURTON

I hereby certify that the above plugging instructions were given as herein stated.

INVOICED  
DATE 12-1-81  
INV. NO. 8085-W

Signed: Merwin Schmidt  
Conservation Division Agent