

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-023-20002-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 16 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
9-16-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Mack Oil Company,

Complete Address: 812 Union Center Building, Wichita, Kansas.

Lease Name Hart Well No. 1

Location CNW-SE-SE Sec. 23 Twp. 4 Rge. (E) (W) 42

County Cheyenne Total Depth 5207'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 4:30PM Day 12 Month 9 Year 1968

The Above well was plugged as follows:

382'--8 5/8" Surface casing, cement circulated with 325 Sx.  
Top of Dakota section @ 2250'.

Circulated hole with heavy mud. Pulled DP to 2475' and displaced 100 Sx. cement thru  
DP from 2475' to 1950'. Pulled DP to 395' and displaced 25 Sx. cement thru DP from  
395' to 315'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/16/68  
INV. NO. 8467-u

Signed: N. D. Nichols  
Well Plugging Supervisor