

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-00455-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 1973
CONSERVATION DIVISION
Wichita, Kansas
10-9-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Bankoff Oil Company,

Complete Address 1119 Sherman, Great Bend, Kansas.

Lease Name Hill Well No. B-1

Location SW-SW-NW Sec. 2 Twp. 5 Rge. (E) (W) 20

County Phillips Total Depth 3406'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company, Inc.,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 7:30 PM Day 5 Month 10 Year 1973

The above well was plugged as follows:

198'--8 5/8" Surface casing, cement circulated with 125 Sx.
3403'--5 1/2" Production casing cemented on bottom with 125 Sx. No plug-back indicated.
Top perforations from 3155' to 3158'.

Sanded well back to 3100' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
(2330') and squeezed well initially with 5 sacks hulls and 25 sacks gel then 70 Sx.
cement and followed with 10 sacks gel and finally 50 Sx. cement to bottom of cellar.
Maximum pump-in pressure-400#. Final shut-in pressure-250#. (Mudding and cementing
by allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/9/73

INV. NO. 4998-W

Signed: W. L. Nichols
Well Plugging Supervisor