

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

15-147-00944-00-00

OCT 17 1975

CONSERVATION DIVISION
Wichita, Kansas

10-17-75

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Bankoff Oil Company

Complete Address Box 5, Pawnee Rock, Kansas 67567

Lease Name Hill "A" Well No. 2

Location NW BW SW Sec. 2 Twp. 5 Rge. (E) (W) 20

County Phillips Total Depth 3432

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor SW Casing Pulling Co.

Address Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 10:15 A Day 15 Month 10 Year 1975

The above well was plugged as follows:

Total Depth 3432' 8 5/8 csg set 232' cwc 200 sk.

5 1/2 csg set 3425' cw 125 sk cem.

5 1/2 csg PFS (3181-3222)

Filled 5 1/2 csg W/sd (3432-3125) dumped 4 sk cmt W/dump bailer. (3125-3095)

Cutoff & recovered 2100' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -70 sk 50-50 poz 6% -

10 sk gel & water -released 8 5/8 plug & pumped 30 sk 50-50 poz 6%. PP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/20/75

INV. NO. 2084-W

Signed: [Signature]
Well Plugging Supervisor