

DISTRICT CONSERVATION AGENT'S REPORT

15-147-79 105-00-00

*BR*

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 64-17

LOCATION SE SW SE

SEC. 24 TWP. 5 RGE. 18

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease G. Jones

Operator Shawver & Armour, Inc. Address 817 Cent Bldg Wichita,

Field \_\_\_\_\_ County Phillips

Total Depth 3340 Feet.

Plugging Contractor Miller Casing Pulling Co

Plugging Contractor's License No. 12

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 115' circulated with cement - 4 1/2" ~~SA~~ 3340' with 75 sax  
cement behind - P.B. to 3192' - perforated 3160'.

Filled with sand to 3140', set 4 sax cement with dump bailer, pulled  
575' 4 1/2" to 560', circulated hole with heavy mud (Gel) - displaced  
20 sax cement through 4 1/2" at 575', heavy mud to 120', displaced  
15 sax cement through 4 1/2" at 120', heavy mud to 35', set rock and  
10 sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

*Edna Perry*  
District Conservation Agent

Date 1-3-58

RECEIVED  
JAN 8 1958  
COMMISSION  
DIVISION  
Wichita, Kansas  
*1-8-58*

PLUGGING  
FILE SEC 24 S R 18W  
BOOK PAGE 64 LINE 17