

DISTRICT CONSERVATION AGENT'S REPORT

15-147-00814-00-00

R

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 71-4

LOCATION SW SE SE

SEC. 24 TWP. 5 RGE. 18

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 212 Lease Jones

Operator Shawver & Armour, Inc. Address 817 Central Bldg Wichita, Kans

Field _____ County Phillips

Total Depth 3270 Feet.

Plugging Contractor Earl Miller Casing Pulling & Sun Cementing

Plugging Contractor's License No. 12

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 136' circulated with cement - 4 1/2" 3270' with 150 sax
cement behind - P.B. to 3210', perforations 3128'.

Filled with sand to 3110', set 4 sax cement with dump bailer, started
580' 4 1/2" - circulated hole with heavy mud through 4 1/2" at 570' (Gel),
displaced 20 sax cement through 4 1/2" at 570', heavy mud to 135',
displaced 15 sax cement through 4 1/2" at 135', heavy mud to 35', set
rock bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Edwin Kelly
District Conservation Agent

Date 1-6-58

PLUGGING
FILE SEC 24 T 5 R 18
BOOK PAGE 71 LINE 7

RECEIVED
STATE CORPORATION COMMISSION
1-9-58
JAN 9 1958
CONSERVATION DIVISION