

R  
KANSAS  
STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION

MAY 17 1960

CONSERVATION DIVISION AGENT'S REPORT

15-147-00156-00-00

CONSERVATION DIVISION  
Wichita, Kansas

517-60

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Phillips

Location: SE NE NE Sec. 25 Twp. 5 Rge. 18 (E) (W) \_\_\_\_\_

Name of Field: \_\_\_\_\_ Total Depth: 3164

I have this date completed supervision of plugging of:

Lease Name: Donaldson Well No. 1

Operator's Full Name: V. E. Sheffer

Complete Address: Russell, Kans

Plugging Contractor: Barnes & Sons Pipe Pulling

Address: Russell, Kans License No. 9

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 6PM Day 12 Month 5 Year 60

The above well was plugged as follows:

13" 870' - 10" 1340' - 7" 2990' - 5 1/2" liner.

Pulled 2650' 7" - 1100' 10" - 587' 13" -

Run 1" tubing in hole to 485', circulated hole with heavy mud through 1"

41 sax gel) - displaced 30 sax cement through 1" at 485', heavy mud to

150' - displaced 30 sax cement through 1" at 150', heavy mud to 25', set

20 sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: Jewel Ogden  
Conservation Division Agent

Reviewed: J. Lewis Brock  
Field Supervisor

Remarks:

INVOICED  
DATE 5/17/60  
INV. NO. 1372-u