

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

13-147-01000-00-00

RECEIVED
STATE CORPORATION COMMISSION

MAR 4 1966
3-4-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name P. M. I

Complete Address: 1515 Wichita Plaza - Wichita Kans

Lease Name Armstrong Well No. 2

Location C-7-7-NE Sec. 3 Twp. 5 Rge. 18 (E) (W)

County Phillips Total Depth 2392

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Red Tiger Drilling

Address: Russell License No. _____

Operation Completed: Hour 8a Day 3 Month 3 Year 1966

The Above well was plugged as follows:

Total Depth 2392 8 5/8 set at 195' @
Gunned pits circulated hile with heavy mud, set cementing plug at 540 ft.,
and displaced 20 sac cement thru drill pipe; heavy mud to 180 ft., set
cementing plug and displaced 20 sac cement, heavy mud to 40 ft., set
cementing plug $\frac{1}{2}$ sac hulls and 10 sac cement, cemented to base of cellar.

I hereby certify that the above well was plugged as herein stated, Gilbert P. Leiker

INVOICED

Signed: Gilbert P. Leiker
Well Plugging Supervisor

DATE 3/4/66
INV. NO. 2820-w