

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -147-20182-00-00 of this well)

Operator's Full Name Rains & Williamson Oil Co., Inc.

Complete Address 425 Page Ct., 220 W. Douglas, Wichita, Kansas 67202

Lease Name Shaw Well No. 1

Location NE NE NE Sec. 10 Twp. 5 Rge. (E) (W) 18

County Phillips Total Depth 3321'
~~3297'~~

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. tools by Sun Cementing Co.

Address License No.

Operation Completed: Hour 1:30 A Day 18 Month 10 Year 1978

The above well was plugged as follows:

Total Depth 3321' ~~3297'~~ 8 5/8 csg set 217' cwc 160 sk.

4 1/2 csg set 3297' cw 150 sk cmt

4 1/2 csg PFS (3200'-04') (3222'-26') (3238'-40')

Set 4 1/2 PP at 3000' Cutoff & recovered 996' of 4 1/2 csg.

Sun Cementing Co. mixed & pumped down 8 5/8 csg with 15 sk gel & water W/300 lbs

hulls, followed with 70 sk 50-50 poz 2% -displaced with 15 sk gel & water & released

8 5/8 plug & capped with 70 sk 50-50 poz 2% & shutin. FPP 300 lbs.

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1978
10-19-78
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 10-20-78

INV. NO. 8339-W