

KANSAS

 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-20019-0000

RECEIVED  
STATE CORPORATION COMMISSION

NOV 7 1967

11-7-67

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Bankoff & Leben

Complete Address: Drawer 2479 Tulsa, Okla.

Lease Name \_\_\_\_\_ States \_\_\_\_\_ Well No. 1

Location \_\_\_\_\_ SW SW NE \_\_\_\_\_ Sec. 10 Twp. 5 Rge. 20 (E) \_\_\_\_\_ (W) X

County Phillips Total Depth 3480

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Leben Drilling Co. Inc.

Address: Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 4:15 P Day 5 Month 11 Year 1967

The Above well was plugged as follows:

RTD 3480' 8 5/8 csg set at 220' cwc 175 sc.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 100 sc cem.  
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 25 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed:   
Well Plugging Supervisor

INVOICED  
DATE 11/8/67  
INV. NO. 6642-W