

R

DISTRICT CONSERVATION AGENT'S REPORT

15-147-01033-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

W

FILE NO. _____
LOCATION NE NW NE
NE-NE-SE
SEC. 10 TWP. 5 RGE. 20W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Buckley
Operator Helmreich & Payne ^{INC.} Address #415 Phil Tower Bldg - Tulsa Okla
Field _____ County Phillips
Total Depth 3464 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 165 ft - cemented all around
7 1/2 in casing set at 3439 ft & cemented with 125 sacks cement
7 in casing Perforated at 3144 to 3166 ft & K City lime
tested - Plug put in at 3199 & 5 sacks of cement
Plug at 3600 ft & 15 sacks of cement - Plug at 165 ft
& 20 sacks of cement - Surface Plug 20 ft below surface
& 10 sacks of cement - Heavy Mud between all Plugs
2600 ft of 7 1/2 in casing Pulled -
Cement put in Hole with
Mumps Bail &

C. M. Strick
District Conservation Agent
Date 6-21-47 JUN 23 1947

PLUGGING
FILE SEC 10 T 5 R 20W
BOOK PAGE 115 LINE 45

6-23-47 7