

15-147-19111-00-00

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 44-1
LOCATION CSW NE *NE*
SEC. 14 TWP. 5 RGE. 20

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease _____ Rundle Box 186
Operator Cities Service Co Address Great Bend, Kans
Field _____ County Phillips
Total Depth 3465 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 207' circulated with cement - 5 1/2" at 3465' with 100 sax
behind. Top cement in 5 1/2" 3432', top perforations at 3246',
Filled with sand to 3240', set 4 sax cement with dump bailer,
pulled 2616' 5 1/2", filled hole with mud to 200', set rock bridge
and 15 sax cement, filled with mud to 35', set rock bridge and
10 sax cement to bottom cellar

PLUGGING
FILE SEC 14 15 R 200
BOOK PAGE 48 LINE 1

RECEIVED
STATE CORPORATION COMMISSION
DEC 18 1950
CONSERVATION DIVISION
[Signature]
District Conservation Agent
Date 12-9-50 12-18-50