

DISTRICT CONSERVATION AGENT'S REPORT

15-147-00585-00-00

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 125-19
LOCATION NE SE NW
SEC. 14 TWP. 5 RGE. 20

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 7 Lease Templeton

Operator Cities Service Oil Co. Address Russell, Kans

Field _____ County Phillips

Total Depth 3509 Feet.

Plugging Contractor J. Shull Pipe Pulling

Plugging Contractor's License No. 8

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 205' circulated with cement - 5 1/2" at 3508' with

150 sax cement behind - perforated at 3210'.

Filled with sand to 3200', set 4 sax cement with dump bailer,

pulled 2140' 5 1/2" - filled with mud to 200', set rock and 15 sax

cement - mud to 35', set rock and 10 sax cement to bottom cellar.

Edward P. ...
District Conservation Agent

Date 6-16-55

PLUGGING
FILE SEC 14 T 5 R 20
BOOK PAGE 25 LINE 14

6-22-55