

KANSAS

*2*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-20160-00-00

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

1-2-73  
RECEIVED  
STATE CORPORATION COMMISSION  
JAN 2 1973  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Leland R. Baird

Complete Address First National Bank, Logan, Kansas

Lease Name Baird Well No. 1

Location C N/2 NW SW Sec. 11 Twp. 5 Rge. (E) (W) 20

County Phillips Total Depth 3529'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Abercrombie Drilling

Address Wichita, Kansas License No.       

Operation Completed: Hour 5:20 A Day 29 Month 12 Year 1972

The above well was plugged as follows:

RTD 3529' 8 5/8 csg set at 210' cwc 175 sx. Cmt. Mat. 50-50 poz cmt W/6% T. gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk ~~W~~

cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massup  
Well Plugging Supervisor

INVOICED

DATE 1/3/73

INV. NO. 6803-W