

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

18-147-20140-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 22 1971
CONSERVATION DIVISION
Wichita, Kansas
11-22-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Capitol Oil Corporation
Complete Address 250 Sutton Place Wichita, Kansas
Lease Name Mitchell Well No. 1
Location NW NW NE Sec. 11 Twp. 5 Rge. (E) (W) 20
County Phillips Total Depth 3258'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Abercrombie Drilling
Address Wichita, Kansas License No.
Operation Completed: Hour 3 P Day 18 Month 11 Year 1971

The above well was plugged as follows:

RTD 3258' 8 5/8 csg set at 213' cwc: Cmt. Mat. 50-50 poz W/4% added gel/
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Measey
Well Plugging Supervisor

DATE 11-29-71
INV. NO. 4692-W