

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-20091-00-00  
Spot: SW Sec/Twnshp/Rge: 2-28S-33W  
1250 feet from S Section Line, 1250 feet from W Section Line  
Lease Name: ANSHUTZ A UNIT TWIN Well #: 2  
County: HASKELL Total Vertical Depth: 2975 feet

Operator License No.: 5208  
Op Name: EXXONMOBIL OIL CORP  
Address: 14950 HEATHROW FORREST PARKWA  
HOUSTON, TX 77210

CIBP Size: feet: 2630 WITH 2 SX CMT  
CIBP Size: feet: 2865  
PROD Size: 5.5 feet: 2975 WITH 420 SX CMT  
SURF Size: 8.625 feet: 624 WITH 350 SX CMT

A  
9/6/04

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/05/2004 1:30 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: GREG ZERR Company: EXXON MOBIL Phone: (620) 544-5534

Proposed Plugging Method: SET CIBP @ 2630' WITH 2 SX CMT. PLUG AT 800' WITH 100 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/05/2004 5:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMPED 500# HULLS WITH 25 SX CMT TO PLUG BOTTOM. PLUG SLIPPED.  
TAGGED CMT AT 2680' SET CIBP @ 2630' WITH 2 SX CMT. 1ST PLUG PULL TO  
800'. LOAD HOLE WITH MUD & PUMP 100 SX CMT. GOOD CIRCULATION. 2ND  
PLUG PULL TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2482	2797		
3	674		

RECEIVED  
NOV 15 2004  
KCC WICHITA

Remarks: USED COMMON CEMENY BY SARGENTS. RECOVERED 820' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
NOV 10 2004  
KCC Dodge City

Signed Jim Holland (TECHNICIAN)

INVOICED  
DATE 11-15-04  
INV. NO 2005060813

Form CP-2/S