

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20603-00-01
Spot: SENW Sec/Twnshp/Rge: 35-34S-37W
2450 feet from N Section Line, 2450 feet from W Section Line
Lease Name: LYNCH 1 UNIT Well #: 2
County: STEVENS Total Vertical Depth: 3210 feet

Operator License No.: 5208
Op Name: EXXONMOBIL OIL CORP
Address: 14950 HEATHROW FORREST PARKWA
HOUSTON, TX 77210

PROD Size: 5.5 feet: 3210 WITH 655 SX CMT
SURF Size: 8.625 feet: 795 WITH 290 SX CMT

#104³³

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/09/2004 8:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Revd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed
Plugging
Method:

PUMP 600# HULLS & 25 SX CMT. PLUG AT 840' WITH 50 SX CMT. PLUG AT 80-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 11/09/2004 5:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

PBTD 3191'. PUMP 600# HULLS & 25 SX CMT TO PLUG PERFS FROM 3049-2849'.
RAN TUBING TO 840 & SPOT 50 SX CMT. PLUG AT 80-0' WITH 10 SX CMT.
CIRCULATE CMT TO SURFACE. PUMP 10 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS.
PRESSURED UP TO 500#.

Perfs:


Top	Bot	Thru	Comments
3049	3090		

RECEIVED
NOV 15 2004
KCC WICHITA

Remarks: USED COMMON CEMENY BY SARGENTS. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Steve Durrant

(TECHNICIAN)

INVOICED

DATE 11-15-04
INV. NO. 2025060813

Form CP-2/3