

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-01012-00-02
Spot: SWNW Sec/Twnshp/Rge: 27-27S-19W
3300 feet from S Section Line, 4620 feet from E Section Line
Lease Name: BRENSING B OWWO Well #: 5
County: KIOWA Total Vertical Depth: 4913 feet

Operator License No.: 5118
Op Name: TGT PETROLEUM CORPORATION
Address: 7570 W 21ST ST N, STE1010D PO BOX
WICHITA, KS 67275

PROD Size: 5.5 feet: 4908 WITH 210 SX CMT
SURF Size: 8.625 feet: 320 WITH 300 SX CMT

\$159⁶⁷

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/04/2004 11:45 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: JERRY SULLIVAN Company: TGT PETROLEUM Phone: (316) 773-2266

Proposed Plugging Method: SAND TO 4378' & 5 SX CMT. PLUG AT 1250' WITH 12 SX GEL & 50 SX CMT. PLUG AT 350' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/04/2004 1:45 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4844'. SANDED BACK TO 4378' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 1250' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4825	4828		
4479	4481		

RECEIVED
NOV 12 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND. RECOVERED 2700' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

(TECHNICIAN)

INVOICED

DATE 11-12-04
INV. NO. 2005060802