

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20146-00-00
Spot: E2SENE Sec/Twnshp/Rge: 35-28S-21W
3300 feet from S Section Line, 330 feet from E Section Line
Lease Name: FLETCHER Well #: 1
County: FORD Total Vertical Depth: 5034 feet

Operator License No.: 5893
Op Name: PRATT WELL SERVICE, INC.
Address: PO BOX 847
PRATT, KS 67124

CIBP Size: feet: 4955 WITH 2 SX CMT
PROD Size: 4.5 feet: 5020
SURF Size: 8.625 feet: 565

163⁶¹

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/08/2004 8:45 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GAROLD INSLEY Company: PRATT WELL SERVICE, INC. Phone: (620) 672-2531

Proposed Plugging Method: CIBP @ 4955' WITH 2 SX CMT. PLUG AT 1450' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/08/2004 10:15 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

CIBP @ 4955' WITH 2 SX CMT. 1ST PLUG AT 1450' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 600' & SPOT 50 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5020	5034	OH	

RECEIVED
NOV 15 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2310' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
NOV 12 2004
KCC Dodge City

Signed

[Signature]
(TECHNICIAN)

INVOICED
DATE 11-15-04
INV. NO. 2005060817

Form CP-24