

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-075-20511-00-00  
Spot: SENWNW Sec/Twnshp/Rge: 23-23S-40W  
4030 feet from S Section Line, 4030 feet from E Section Line  
Lease Name: HERRMAN Well #: 1-23  
County: HAMILTON Total Vertical Depth: 2560 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: PO BOX 18496 6200 N WESTERN AVE.  
OKLAHOMA CITY, OK 73154

PROD Size: 4.5 feet: 2559 WITH 700 SX CMT  
SURF Size: 8.625 feet: 328 WITH 200 SX CMT

#83<sup>20</sup>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/10/2004 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: MIX & PUMP 4 SX HULLS, MIX & PUMP 225 SX 60/40 CMT W/6% GEL, WOC 30 MIN., TOP OFF IF NECESSARY, TIE ONTO 4-1/2" & 8-5/8" ANNULUS, ATTEMPT TO ESTABLISH PUMP IN, FILL IN IF ABLE TO PUMP INTO ANNULUS, WELD ON CAP, CLEAN UP LOCATION.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/10/2004 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CMT TOP OF 4 1/2" CASING @ 340'. PUMP 150 SX CMT & 400# HULLS. PRESSURED UP TO 1000# & HELD. PUMP 40 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS. PRESSURE TO 500# & HELD.

Perfs:


Top	Bot	Thru	Comments
2511	2526		

RECEIVED  
NOV 15 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

*Ken Jehlik*

(TECHNICIAN)

INVOICED

DATE

11-15-04

INV. NO

2005060812

*[Signature]*  
Form CH-33